

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 10 Twp. 21S Rge. (E) 16 (W)
Location as "NE/CNW%SW%" or footage from lines SW SW NE
Lease Owner Pickrell Drilling Company
Lease Name Boyd Well No. 1
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 4, 1965
Application for plugging filed April 4, 1965
Application for plugging approved April 4, 1965
Plugging commenced April 4, 1965
Plugging completed April 4, 1965
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3869 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1003'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 350', set plug, cemented with
25 sacks cement. Heavy mud to 225 feet, set
plug, cemented with 25 sacks; heavy mud to
35 feet, set plug, cemented with 10 sacks
cement to bottom of cellar. Plugged rat
hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1965
CONSERVATION DIVISION
Wichita, Kansas

4-21-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts (employee of ~~owner~~ owner) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th National Bank Building, Wichita 2, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of April, 1965

My commission expires June 21, 1966
Maxine Blackman Notary Public.

ROTARY DRILLING LOG

15-145-30010-0000

COMPANY: -PICKRELL DRILLING COMPANY
705 4th National Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 3-22-65

Rotary Drilling Completed 4--3-65

LOCATION: BOYD No. 1, SW SW NE Section 10-21-16W, Pawnee County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (45 jts) 8 5/8" surface casing set at 1003' with 425 sacks cement. Circulated. Completed 10 A.M. March 23, 1965. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

280	Sandy Clay	<u>C. F. S.</u>
425	Blue Shale	3470
535	Sand	3485
575	Red Bed	3597
588	Sand	3540
750	Red Bed & Sand Streaks	3730
830	Red Bed & Sand	3810
950	Shale & Sand Streaks	3817
998	Shale, Red	3822
1725	Shells & Shale	3869
2100	Shale & Lime	
2230	Lime	
3150	Shale & Lime	<u>Slope Tests</u>
3630	Lime	2000
3700	Lime & Shale	2500
3763	Lime	3000
3771	Lime & Chert	3500
3812	Simpson	
3869	Arbuckle - RTD	<u>S. L. M.</u>
		2670
		2895
		3405

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1965
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, G. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 7th day of April, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966.

[Signature]
Maxine Blackman, Notary Public