

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 2 TWP. 21S RGE. 16W E/W
Location as in quarters or footage from lines:

C SE NE

Lease Owner Brougher Oil, Inc.

Lease Name Mermis B #1 Well No. _____

Office Address P.O. Drawer 1367 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced _____ 1-19-82

Plugging completed _____ 1-25-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 3797'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1017'	none
				5-1/2"	3794'	3061'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3575' and set 7 sacks cement. Shot casing @3187
and 3067. Pulled a total of 76 joints of pipe. Plugged well with 5 sacks ~~XXXXX~~ gel,
2 sacks hulls, 15 sacks gel, 2 sacks hulls, 70 sacks cement, 10 sacks gel, 8-5/8"
plug, 90 sacks 50/50 pos, 4% gel, 3% cc. Plugging complete

1-28-82

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1982

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

CONSERVATION DIVISION
Wichita Kansas


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1982

My Commission expires:



Irene Hoover
Notary Public.

U

1950