

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty Company, Inc.

Complete Address: 800 Bitting Building Wichita, Kansas 67202

Lease Name Phinney Well No. 1

Location NW NW NW Sec. 12 Twp. 21 Rge. 16 (E) (W) X

County Pawnee Total Depth 3788'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ralph Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 12 Day 10 Month 10 Year 1968

The Above well was plugged as follows:

Total Depth 3788' 8 5/8 csg set at 974' cwc 475 sc.

5 1/2 csg set at 3784' cw 100 sc cmt.

Filled 5 1/2 csg with sand (3760-3788) Dumped 5 sc cmt with dump bailer. (3720-3760)

Shutoff and recovered 3010' of 5 1/2 csg.

Mud to <sup>400</sup> 575'. Set plug and rock bridge (385-400)

Dumped 6 yds readymix cmt. (0-385)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rio F. Murray  
Well Plugging Supervisor

DATE 10/11/68

INV. NO. 8608-11