

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CWL
~~NE-NE-NE~~

SEC. 12 TWP. 11 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. #2 Lease S. Smith

Operator Anderson & Pritchard Oil Co. Address Box 142 - A Bend, Kans -

Field _____ County Pawnee

Total Depth 3783 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 950 ft. Circulated with cement
4 1/2 casing set at 3776 ft. Cemented with 100 sacks of
cement. Plugged back to 3770 ft. with chat. dumped
4 sacks of cement at 3770 ft. Shot off & pulled the
4 1/2 casing. mud to 250 ft. P.W. Brock. Bridger &
15 sacks of cement at 250 ft. mud to 30 ft
Plug & 20 sacks of cement at the surface.

RECEIVED

STATE CORPORATION COMMISSION

MAR 13 1951 3-13-51

CONSERVATION DIVISION
Wichita, Kansas

E. M. Stough
District Conservation Agent

Date 3-10-51

PLUGGING
FILE SEC 12 T 11 R 16
PAGE 68 LINE 20