

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9-16-69

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bovaird Supply Company

Complete Address Box 2590 Tulsa, Oklahoma 74101

Lease Name Haney Well No. 1

Location SW NW NW Sec. 13 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3814'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 3P Day 11 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 3814' 8 5/8 csg set at 979' cwc 475 sk.

5 1/2 csg set at 3809' cw 50 sk cmt.

Filled 5 1/2 csg W/sd (3800-3814) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Cutoff and recovered 2935' of 5 1/2 csg.

Mud to 400' rock and sand (375-400)

4 yds readymix (0-375)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/16/69

INV. NO. 478-4