

KANSAS
STATE CORPORATION COMMISSION

R

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 106-31 County: PAWNEE

Location: NE-SE-SE Sec. 13 Twp. 21 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3896'

I have this date completed supervision of plugging of:

Lease Name: GORE Well No. 1

Operator's Full Name: NADEL + GUSSMAN

Complete Address: 1714 1ST NATL BLDG TULSA 3, OKLA

Plugging Contractor: FORBES CASING PULLING

Address: _____ License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 7:00^{PM} Day 27 Month JUNE Year 1958

The above well was plugged as follows:

8 7/8" - 946' w/450 5X CMT CIRC - 5 1/2" - 3894 w/100 5X
TOP PERFORATION - 3812' -
SANDS HOLE BACK TO 3800' w/5 5X CMT PLUG
THROUGH BRILER - SHOT + PULLED PIPE - FILLED
HOLE w/MUD TO 250' - SET 10' ROCK BRIDGE - w/20
5X CMT PLUG - MUDDED TO 40' - w/10' ROCK
BRIDGE - CAPPED TO BASE OF CELLAR w/10
5X CMT.

Signed: Frank Broughton
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

7-7-58

PLUGGING
FILE SEC. 13 T. 21 R. 16
BOOK PAGE 106 LINE 31