

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 9 - 1965
8-9-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name O. A. Sutton
Complete Address: 407 Insurance Bldg Wichita, Kans
Lease Name Hunsley Well No. 1
Location CSWC NW Sec. 22 Twp. 21 Rge. (E) (W) 16
County Pawnee Total Depth 3870
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Gabbert & Jones Drg Co
Address: Wichita, Kans License No.
Operation Completed: Hour 12:30AM Day 2 Month 8 Year 65

The Above well was plugged as follows:

8 5/8" 994' circulated with 450 sax cement.
Circulated hole with heavy mud, set plug at 420', displaced 20 sax
cement through drill pipe, heavy mud to 180', set plug and
displaced 20 sax cement through drill pipe, heavy mud to 35'
set plug, hulls and filled to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/9/65
INV. NO. 1589-W

Signed: *Edson Peery*
Well Plugging Supervisor