

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9-5-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address P. O. Box 590 Tulsa, Oklahoma 74101

Lease Name Wedel "B" Well No. 1

Location SE SE NE Sec. 14 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3826

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 4P Day 4 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 3826' 8 5/8 csg set at 968' cwc 475 sk.

5 1/2 csg set at 3822' cw 125 sk cmt.

Filled 5 1/2 csg W/sd (3800-3826) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Cutoff and recovered 2930' of 5 1/2 csg.

Mud to 400' set rock bridge (375-400')

Dumped 5 yds readymix cmt. (0-375)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/5/69
INV. NO. 411-W

Signed: Leo F. Messing
Well Plugging Supervisor