

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1969
CONSERVATION DIVISION
Wichita, Kansas

9-2-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bovaird Supply Company

Complete Address P. O. Box 2590 Tulsa, Oklahoma 74101

Lease Name Wedel Well No. 1

Location NE NE SE Sec. 14 Twp. 21 Rge. (E) (w) 16

County Pawnee Total Depth 3920'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling, Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 4P Day 29 Month 8 Year 1969

The above well was plugged as follows:

Total Depth 3920' 8 5/8 csg set at 963' cwc.

5 1/2 csg set at 3900' cwr 150 sk cmt.

Filled 5 1/2 csg W/sd (3875'-3920') Dumped 5 sk cmt W/dump bailer/ (3880-3920)

Cutoff and recovered 3095' of 5 1/2 csg.

Mud to 400' set rock bridge (375-400)

Filled to surface with 5 yds readymix cmt. (0-375)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bud F. Massey
Well Plugging Supervisor

DATE 9/2/69
INV. NO. 390-W