

15.145-01396-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1963

11-21-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Forbes Casing Pulling Co

Complete Address: Box 221 Great Bend, Kansas

Lease Name M. M. Fox Well No. 1

Location SW SW SW Sec. 23 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3859

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: same

Address: License No.

Operation Completed: Hour 4PM Day 19 Month 11 Year 63

The Above well was plugged as follows:

8 5/8" 987' circulated with cement - 5 1/2" ~~2848~~ 3856' with 125 sax cement
Filled with sand to 3840', set 4 sax cement with dump bailer - pulled 2846'
5 1/2" - pumped hole full heavy mud (40 sax Gel) pumped wiper plug followed
by 100 sax cement.

Mudding and cementing by Forbes Company Pump truck 700# pumping pressure &
500# standing pressure on completion.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Kelly*
Well Plugging Supervisor

DATE 9/6/63
INV. NO. 9405-w