

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County. Sec. 26 Twp 21S Rge 22W (X) (W)

Location as "NE/CNW%SW%" or footage from lines C NW SW

Lease Owner Brandt-Clark Oil Company

Lease Name Stegman Well No. 1

Office Address 505 1st National Bank Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 29 19 69

Application for plugging filed verbal w/Agent Sept. 28 19 69

Application for plugging approved October 1 19 69


Plugging commenced 6:30 A. M. September 29 19 69

Plugging completed 7:15 A.M. September 29 19 69

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves

Producing formation Depth to top Bottom Total Depth of Well 4550 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	463'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well Plugged with pump truck by Allied Cementing Co., Inc.

1st Plug Set @ 650 ft. w/80 sx cement

2nd Plug Set @ 45 ft. w/15 sx. cement.

10-6-69  
RECEIVED  
STATE CORPORATION COMMISSION  
OCT 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cement Co., Inc.

Address Box 207 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Earl O. Brandt (employee of owner) or owner or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl O. Brandt

Earl O. Brandt  
Brandt-Clark Oil Company  
505 1st National Bank Bldg. - Wichita, Ks.

SUBSCRIBED AND SWORN to before me this 2nd day of October, 19 69

My commission expires April 29, 1973



Carole J. Paddock  
Notary Public.

DRILLER'S LOG

COMPANY: Brandt-Clark Oil Co.  
 505 First National Building,  
 Wichita, Kansas 67202

CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202

LEASE: #1 Stegman

LOCATION: C NW SW 26-21S-22W, Hodgeman County, Kansas

COMMENCED: September 18, 1969

COMPLETED: September 29, 1969

CASING: Set 8 5/8" Surface Casing @ 463'/260 sacks cement

0-463	Post rock and shale
463-822	Shale
822-836	Anhydrite
886-1469	Red beds and shale
1469-1500	Anhydrite
1500-1825	Shale and red beds
1825-2240	Shale and salt
2240-2360	Shale and lime
2360-2558	Lime and shale (Ft. Riley)
2558-3915	Lime and shale
3915-4255	Lime and shale (Kansas City)
4255-4500	Lime and shale
4500-4550	Mississippi

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 6 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS            )  
                                   )    SS  
 COUNTY OF SEDGWICK        )


I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Stegman, located in C NW SW 26-21S-22W, Hodgeman County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*  
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd dat of October, 1969.

*Wilma Riller*  
 Notary Public - Wilma Riller



My Commission Expires: July 27, 1971.