


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County. Sec. 20 Twp. 21 Rge. 22 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C/SE/SW

Lease Owner Brooks Hall Oil Corporation
Lease Name Brown Well No. 1
Office Address 101 Park Ave. Bldg. Suite 600 Okal City
Character of Well (Completed as Oil, Gas or Dry Hole) 73702
oil



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-17-79 19____
Plugging completed 10-22-79 19____
Reason for abandonment of well or producing formation _____
Depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	324'	none
				4 1/2"	4522'	2393.19

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 4100' and 4 sks cement
Shot pipe at 3000'-2500' and 2400'
Pulled 55 joints 4 1/2" casing
Squeezed well with 1 sk hulls 50 sks 50/50 pozmix cement
15 sks gel, 1 sks hulls, 35 sk cement, 5 sks gel and capped
with 10 sks cement.

11-5-79

RECEIVED
STATE CORPORATION COMMISSION

MAY 05 1979

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
James W. Rockhold, Box 698, Gt. Bend, Ks.
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1979

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. _____

Iona M. Leatherman
Notary Public.

My commission expires 9-28-83

KANSAS DRILLERS LOG

COMPANY Brooks Hall Oil Corporation

SEC. 20 T. 21S R. 22W

FARM Brown

NO. 1

LOC. C-SE SW

COUNTY Hodgeman

ROTARY TOTAL DEPTH 4,523'
COMM. July 19, 1978
CONTRACTOR H-30, Inc.
ISSUED August 1, 1978

COMP. July 28, 1978

CASING

10 3/4"
8 5/8" Set at 324' cemented w/185 sxs cement
5 1/2"
4 1/2" Set at 4,523' cemented w/150 sxs cement

ELEVATION 2,277 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock, Shale and Sand	324'
Shale and Red Bed	910'
Sand	1,130'
Shale	1,452'
Anhydrite	1,516'
Shale	2,203'
Lime and Shale	2,603'
Shale and Lime	2,787'
Lime and Shale	3,180'
Shale and Lime	3,345'
Lime	3,485'
Lime and Shale	3,675'
Shale and Lime	3,864'
Lime	4,523'
Rotary Total Depth	4,523'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 1st day of August, 1978.

RECEIVED
STATE COMMISSION
OCT 15 1979



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
June 25, 1982

JOHN S. WILSON
Notary Public, Kansas