


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 20 Twp. 21S Rge. (E) 22 (W)
Location as "NE/CNW/SW" or footage from lines C. NW/4 SW/4
Lease Owner Pickrell Drilling Company
Lease Name Brittie Brown Well No. 1
Office Address 705 Fourth National Bank Bldg. - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 5, 19 62
Application for plugging filed May 6, 19 62
Application for plugging approved May 6, 19 62
Plugging commenced May 6, 19 62
Plugging completed May 6, 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4623 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 240'. Set Plug, cemented with 20 sacks cement and 1/3 sack hulls. Heavy mud to 35'. Set Plug, cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 9 5 1962

CONSERVATION DIVISION
Wichita, Kansas

5-25-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg. - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss
C. W. Sebitts, Partner (Employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. W. Sebitts, Partner
705 Fourth National Bank Bldg. - Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 62

My commission expires September 24, 1962

Maxine Johnson
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company Rotary Drilling Commenced 4-24-62
 705 Fourth National Bank Bldg.
 Wichita, Kansas Rotary Drilling Completed 5-5-62

LOCATION: Brittie Brown C. NW/4 SW/4
 Section 20-21S-22W
 Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: 250' (6 jts) 8 5/8" 20# Surface Casing Set with 170 sacks cement.
 Circulated--completed 9 P.M.
 No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60 - Post Rock & Clay	<u>Circulating for Samples</u>
250 - Blue Shale & shells	4300'
270 - Shale	4418'
320 - Sand	4463'
360 - Blue Shale	4475'
510 - Sand	4490'
635 - Shale	4505'
845 - Red Beds	4520'
865 - Blaine	4571'
950 - Red Beds	4623'
1140 - Sand	
1305 - Red Beds	
1680 - Red Bed, shale & shells	
1710 - Anhydrite	
2150 - Shale - shells	<u>Slope Test</u>
2325 - Lime - shale	1000' 0°
2765 - Lime	2000' 0°
3406 - Lime - Shale	3000' 0°
3575 - Shale Lime & sand	4000' 0°
3710 - Lime	
3940 - Lime - Shale	
4065 - Lime	<u>S. L. M.</u>
4140 - Lime & Shale	2325'
4200 - Lime	3180'
4255 - Lime - Shale	3824'
4320 - Lime	4475'
4418 - Lime & Shale	
4492 - Lime - Chert	
4502 - Mississippian Dolomite	
4623 - Mississippian Chert - Total Depth	

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 25 1962
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Partner, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
 C.W. Sebitts, Partner Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 24th day of May, 19 62, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, Partner, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

[Signature]
 Maxine Johnson Notary Public