

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Section plot grid for locating the well.

Locate well correctly on above
Section Plot

Hodgeman County, Sec. 6 Twp. 21 Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines C/SW NE

Lease Owner Twin Western Resources, Inc.

Lease Name Carpenter Well No. 1

Office Address Suite 920, Union Center Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 20 19 74

Application for plugging filed December 20 19 74

Application for plugging approved December 20 19 74

Plugging commenced December 20 19 74

Plugging completed December 20 19 74

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Garden City, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4498 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 8-5/8", 0, 310'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 450' with 50 sacks of 60-40 pozmix; plugged at 240' with 25 sacks of 60-40 pozmix; plugged at 40' with hulls and 10 sacks of 60-40 pozmix. Plug down at 1:30 P. M. December 20, 1974.

RECEIVED
STATE CORPORATION COMMISSION
MAY 1975

CONSERVATION DIVISION
WICHITA, KANSAS

3-7-75

Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS COUNTY OF BARTON
Kenneth J. Link (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 26th day of December, 19 74

December 14, 1977
Elaine H. Taylor Notary Public



Judy

D R I L L E R S L O G

#1 Carpenter

CASING:
305.31' of used 8-5/8"
surface casing.

COMPANY: Twin Western Resources, Inc.

DESCRIPTIONS:
C/SW NE
Section 6-21-22W
Hodgeman Co., Kansas

CONTRACTOR: Strata Drilling Company

TOTAL DEPTH:
4498'

COMMENCED: December 12, 1974

COMPLETED: December 20, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Post Rock	0	90	Ran 305.31' of used 8-5/8" surface casing; set and cemented at 310' with 185 sacks of common cement, 2% gel and 3% C. C. Plug down at 5:00 A. M. December 13, 1974.
Shale	90	430	
Shale, Sand & Red Bed	430	1230	
Shale w/Sand Streaks	1230	2165	
Shale & Lime	2165	2275	
Lime & Shale	2275	2700	
Lime	2700	2910	
Lime & Shale	2910	4325	
Lime	4325	4446	
Lime & Shale	4446	4498	
			Ran electric log.

ROTARY TOTAL DEPTH: 4498'

D. & A.

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1975
CONSERVATION DIVISION
Wichita Kansas

Plugged hole as follows: Plugged at 450' with 50 sacks of 60-40 pozmix; plugged at 240' with 25 sacks of 60-40 pozmix; plugged at 40' with hulls and 10 sacks of 60-40 pozmix. Plug down at 1:30 P. M. December 20, 1974.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 26th day of December, 1974.

My Commission Expires:
December 14, 1977

Elaine H. Taylor
Elaine H. Taylor, Notary Public

