

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County. Sec. 22 Twp. 21S Rge. 22W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
100'E C NW SE


Lease Owner Ben Hogan  
Lease Name Wieland Well No. #1  
Office Address P. O. Box 11276, Fort Worth, Texas 76110  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed November 23 1977  
Application for plugging filed November 23 1977  
Application for plugging approved November 23 1977  
Plugging commenced November 23 1977  
Plugging completed November 23 1977  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole plugged with 50-50 pozmix as follows: 50 sacks @ 900', 35 sacks @ 400', 10 sacks @ 40'. Plug down 1:15 a.m., November 23, 1977.

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 8 1977 12-8-77

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.

Kenneth J. Link (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1977.

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-80.



D R I L L E R S   L O G

#1 Wieland

CASING RECORD: 11 jts. new 20# 8-5/8" surface casing	COMPANY: Ben Hogan	DESCRIPTION: 100' E C NW SE Section 22-21S-22W Hodgeman County, Kansas
TOTAL ROTARY DEPTH: 4550'	CONTRACTOR: Strata Drilling Company	ELEVATION: 2271 G.L.
	COMMENCED: November 16, 1977	
	COMPLETED: November 23, 1977	

D & A

---

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock, shale and sand	0	425	Ran 420' new 20# 8-5/8" surface casing; set and cemented @ 420' with 250 sacks common cement, 2% gel, 3% C.C.; cement circulated. Plug down @ 2:40 a.m., November 17, 1977.
Shale and sand	425	1465	
Anhydrite	1465	1498	
Shale	1498	2030	
Shale and lime streaks	2030	2335	
Lime and shale	2335	4305	Ran one electric log.  Hole plugged with 50-50 pozmix as follows: 50 sacks @ 900', 35 sacks @ 400', 10 sacks @ 40'. Plug down 1:15 a.m., November 23, 1977.
Lime	4305	4550	

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 8 1977

STATE OF KANSAS )  
                          ) ss  
COUNTY OF BARTON)

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this 6th day of December, 1977.

My commission expires 3-28-80.

*Loneita Barry*  
Loneita Barry, Notary Public

