


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Pawnee County. Sec. 1 Twp. 21S Rge. (E) 16 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NE
Lease Owner Anderson Prichard Oil Corporation
Lease Name Wise Well No. 2
Office Address Box 142, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed April 9 19 48
Application for plugging filed October 7 19 52
Application for plugging approved October 8 19 52
Plugging commenced October 13 19 52
Plugging completed October 20 19 52
Reason for abandonment of well or producing formation non-commercial
(well making 100% water)
If a producing well is abandoned, date of last production July 11, 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rivas
Producing formation Arbuckle Depth to top 3742 Bottom Total Depth of Well 3792 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	971'	none
				5 1/2"	3785'	2618'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

TD 3792'-3770' Crushed rock
3770'-3740' 5 sacks cement
Shot casing off at 2618' -- pulled casing
Pumped in 25 sacks mud and 200 sacks cement
in surface casing.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anderson Prichard Oil Corporation
Address Box 142, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

G. M. Dougherty (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of October, 19 52

Verdella M. Hankins
Notary Public.

My commission expires Dec. 4, 1954

28-5091-s 8-50-10M

PLUGGING
FILE SEC 1 T 21 R 16
BOOK PAGE 50 LINE 30

10-23-52

CONSERVATION DIVISION

WISE WELL NO. 2

Location: ~~S1/4~~ ~~S21/4~~ NE1/4 Sec. 1-218-16W
Pawnee County, Kansas

Date Spudded: 3/24/48

Operator: Anderson-Prichard Oil Corporation

Date Rotary Completion: 4/9/48

Contractor: Heathman-Honaker Drilling Co., Inc.

Total Depth: 3785' (Rotary)

Surface Casing: 32 jts, 983' of 8 5/8ths" casing
set at 977' and cemented with
450 sacks bulk cement - circulated.

Running 26 and 28 3/4 to 72

Oil String: 123 jts, 3796' of 5 1/2" casing set at 3785
and cemented with 175 sacks bulk cement.

LOG

(Figures indicate bottom of formation)

TOPS

(From Operator)

Shale & shells	0 to	390
Dakota sand		510
Shale & shells		600
Shale		710
Shale & red bed		(955)
Shale & Red Bed		(967)
Anhydrite		990
Shale & shells		1800
Salt		1850
Lime and shales		2155
Sandy lime		2245
Shale & lime shells		2485
Lime & shale		3215
Lime		3740
shale		3750
Lime		3785 TD

Anhydrite	967'
Arbuckle	3742'
T. A.	3788

*Flow 2 1/2 Bopd / 24 hrs
Pump. 9 Bopd + 1% water / 24
hrs.
Pump. 26 Bopd + 8%
water / 24 hrs.*

The undersigned, Heathman-Honaker Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above-noted well as reflected by the Daily Drilling Reports.

HEATHMAN-HONAKER DRILLING CO., INC.

By *R. D. Dancy*
Treasurer

Subscribed and sworn to before me this 15th day of April, 1948.

Richard Hinderly
Notary Public

My Commission Expires: July 2, 1949

*SP 26 Bopd + 8%
water*

PLUGGINS
FILE SEC. 1 T 21 R 16 26
BOOK PAGE 50 LINE 30

RE
STATE CO
001
INFORMATION DIVISION