


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pawnee County, Sec. 1 Twp. 21 Rge. 16 ~~(BY XXX)~~ (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner Anderson-Prichard Oil Corporation  
Lease Name Wise Well No. 1  
Office Address Box 142 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed May 5, 19 47  
Application for plugging filed Sept. 6, 19 51  
Application for plugging approved September 7, 19 51  
Plugging commenced Sept. 11, 19 51  
Plugging completed Sept. 13, 19 51  
Reason for abandonment of well or producing formation Non-Commercial  
If a producing well is abandoned, date of last production July 26, 19 51  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. D. Stough  
Producing formation Arbuckle Depth to top 3751' Bottom Total Depth of Well 3817' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	990'	None
				5-1/2	3810	2058

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back from 3817' to 3754' w/crushed rock and 5 sax cement  
Shot casing off at 2058'. Pulled Casing  
Filled hole with heavy mud to 235'  
Set rock bridge and dumped 15 sax cement  
Filled with heavy mud to 35' from top  
Mixed 15 sax cement for cap on well

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen % Anderson-Prichard Oil Corp.  
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Gerald M. Dougherty (employee of owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) *Gerald M. Dougherty*  
Box 142 - Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 51.

My commission expires December 4, 1954

*W. B. ...*  
STATE CORPORATION COMMISSION  
Notary Public.

28-5081-a 8-50-10M  
**PLUGGING** SEP 21 1951  
FILE SEC L T 21 R 42  
BOOK PAGE 108 LINE 10

WISE WELL NO. 1

Location: Approx. Center NE $\frac{1}{4}$  NE $\frac{1}{4}$  NE $\frac{1}{4}$  1-21S-16W Commenced: 2-25-47  
 Barton County, Kansas  
*PANTEE* Oil String Cemented: 3-15-47

Operator: The Bay Petroleum Corporation Total Depth: 3817'

Contractor: H H & B Drilling Co., Inc.

Casing Record: Surface Casing: 32 Jts. 8-5/8" Rd.Thd. Smls. @ 990'  
 Cemented with 350 sacks cement and 3 CC  
 Oil String: 123 Jts. 5-1/2" OD 14# H-40 8 Rd.Thd. @ 3810'  
 Cemented with 125 sacks cement.

L O G

(Figures indicate bottom of formation)

Surface soil	0 to 10
Clay, sand, shale	120
Shale and shells	395
Sand	520
Shale	525
Shale	715
Shale and red bed	984
Anhydrite	990
Shale and red bed	1375
Shale and salt	1560
Salt	1730
Shale and lime	1835
Shale and shells	2000
Shale	2060
Lime	2090
Lime	2360
Lime, shale	2420
Shale and shells	2850
Lime and shale	3210
Lime	3534
Lime and shale	3568
Lime	3630
Lime and shale	3727
Shale	3754
Arbuckle lime	3801
Lime	3814
Arbuckle lime	3817 T.D.

The undersigned, H H & B Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

H H &amp; B DRILLING CO., INC.

BY: *R. W. Bailey*  
Asst. SecretarySTATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS:

Be it remembered that on this 18th day of March 1947, before me the undersigned, a Notary Public, duly commissioned, in and for the County and State aforesaid, came R. W. Bailey, Asst. Secretary of H H & B Drilling Co., Inc., a corporation of the State of Kansas, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of the same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

**PLUGGING**

FILE SEC 1 T 21 R 16 W

My commission expires BOOK PAGE 108 LINE 10 July 2, 1949.

RECEIVED  
 SEP 21 1947  
*Richard Rindery*  
 Notary Public  
 Wichita, Kansas