

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-20868-0000

LEASE NAME Phinney #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NE NE

SEC. 1 TWP. 21 RGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed \_\_\_\_\_

Plugging Commenced 9/26/84

Plugging Completed 10/4/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Brougner Oil, Inc.

ADDRESS P.O. Drawer 1367, Great Bend, Ks. 67530

PHONE # (316) 793-5610 OPERATORS LICENSE NO. 6393

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3801'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	984'	none
				5 1/2"	3797'	1736'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3738' & 5 sacks cement. Shot pipe at 2800', 2620', 2410', 2206', & 1736'. Pulled 42 joints of pipe. Pulled to 1000', spotted 50 sacks cement, pulled up to 480' & 30 sacks cement, pulled up to 40' & circulated cement to top.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED


STATE OF Kansas COUNTY OF Rice, ss. STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 19 day of October, 19 84



My Commission expires: \_\_\_\_\_



15.145.20868-0000

614 PATTON ROAD P.O. DRAWER 1367  
GREAT BEND, KANSAS 67530  
PHONE (316)793-5610

August 30, 1984

Kelso Casing Pulling  
Box 347  
Chase, KS 67524

Attention: Mr. Darrell Kelso

Dear Darrell:


The information concerning the two wells we would like to have you pull the casing from and plug to abandon is as follows:

Matoush "B" #1: SE SE NW Section 29-16-10, Ellsworth County, Kansas  
8 5/8" Casing set @214'  
4 1/2" Casing welded liner (676') and 2612' collared pipe ran to 3288'  
cemented w/75 sacks; old 5 1/2" shot off @2669'.  
Open hole from 3288' to 3320'  
Perforations: 3200' to 3204'  
3128' to 3131'  
3015' to 3019'

Phinney #1: C NE NE Section 1-21-16, Pawnee County, Kansas  
8 5/8" Casing set @984'  
5 1/2" Casing set @3797'  
T.D. is 3801'  
No perforations in well

If you need additional information, please advise. Thank you for your cooperation.

Yours truly,

  
Joe E. Brougher  
President

JEB/vb

RECEIVED  
STATE CORPORATION COMMISSION

SEP 04 1984

CONSERVATION DIVISION  
Wichita, Kansas