


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 1 Twp. 21 Rge. 16 W/E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines _____

NW SW SW
Lease Owner Braden Deem Inc.
Lease Name Barrett Well No. 1
Office Address 200 East First Wichita Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plat

Oil
Date Well completed _____ 1962
Application for plugging filed 4/ 1979
Application for plugging approved 4/ 1979
Plugging commenced 5/2 1979
Plugging completed 5/15 1979
Reason for abandonment of well or producing formation _____

Dry
If a producing well is abandoned, date of last production _____
4/24 1979
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Arbuckle Depth to top 3775 Bottom 3780 Total Depth of Well 3780
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUL IN	PULLED OUT
	Surface	0	987	8 5/8		
		0	3775	5 1/2		2808

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand 50 ft. & dumped 5 sx. cement

Set plug at 400 ft. & filled to bottom of cellar with 5 yds. Readymix cement.

5-18-79

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1979

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Nicholas Casing Pulling
Box 273 Geneseo Kansas 78444
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE ss.
George A. Nicholas (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas



Subscribed and Sworn to before me this 17th day of May 19 79

My commission expires August 29, 1982

(Address) Steven K Prickett

Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALPINE OIL & ROYALTY CO., INC.
Farm- Barrett No. 1

SEC. 1 T. 21 R. 16W
NW SW SW

Total Depth. 3780'
Comm. 10-27-62 Comp. 11-4-62
Shot or Treated.
Contractor. Quaker Drlg. Co., Inc.
Issued. 4-13-63

County Pawnee
KANSAS



CASING:
8 5/8" 987' cem w/500 sx.
5 1/2" 3775' cem w/100 sx.

Elevation. 1974' KB

Production. 120 BOPD, NW

Figures Indicate Bottom of Formations.

surface soil	20
sand	50
clay	70
gravel	95
shale & shells	408
Dakota sand	520
shale	525
red bed, shale & sand	850
red bed	977
anhydrite	1005
red bed	1030
shale & shells	1650
shale & sandy lime	1940
lime & shale	3050
lime	3325
shale	3415
lime	3675
cherty lime	3739
lime	3780 RTD
Total Depth	

TOPS:	
Heebner	3323
Brown Lime	3415
Lansing	3424
Base Kansas City	3666
Viola	3689
Simpson	3746
Arbuckle	3774

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1979

CONSERVATION DIVISION
Wichita, Kansas

YOUR COPY