

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 82-28 Location: NW-NW-NW

County: PAWNEE Sec. 19 Twp. 21 Rge. 15 (W)

Name of Field or Pool: _____ Total Depth: 3910

I have this date completed supervision of plugging of:

Well No. 1 Lease BIRD

Operator's Full Name NADEL + GUSSMAN

Complete Address: 1714 1ST NATL. BANK BLDG, TULSA 2, OKLA.

Plugging Contractor: FORBES CASING PULLING CO

Address: GT BLVD, KANSAS License No. 49

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 4:30 PM Day 21 Month 2 Year 58

The above well was plugged as follows:

8 7/8 - 950' CWC - 5 1/2. 3909 w/100 SX CMT - TOP PERFORATION - 3810'
SANDS BOTTOM OF HOLE TO 3640' - PLACED 5 SX
CMT ON SAND THROUGH BAILER - PULLED PIPE -
FILLED W/MUD TO 300' SET ROCK BRIDGE W/20
SX CMT - FILLED HOLE W/MUD TO 35' SET BRIDGE
W/10 SX CMT CAP TO BASE OF CELLAR -

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: Frank Burdick
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STAT. CORPORATION COMMISSION
3-8-58
MAR 8 1958
CONSERVATION DIVISION
Wichita, Kansas

Reviewed: J. Lewis Brook
Field Supervisor

Remarks:

Signed: _____
Well Plugging Supervisor

PLUGGING
FILE SEC 19 T 21 R 15 W
BOOK PAGE 82 LINE 28