

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21050-0000

C SE SE, Sec. 21, T 21 S, R 15 W/W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Kasselman Well # 1

Operator: L.D. Drilling Co. Inc
Name & Address: Rt. 1
Box 183-B
Great Bend KS. 67530

County Pawnee
Well Total Depth 3899 feet \$126.72
Conductor Pipe: Size _____ feet _____
Surface Casing: Size 8 5/8 feet 918'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. + W. Well Servicing License Number 6901

Address Box 231, 403 W. Front Clatlin KS 67525

Company to plug at: Hour: 9:30 am Day: 28 Month: September Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Robert L. Strube

(company name) D.S. + W. Well Servicing (phone) _____

were: To use 60/40 pozmix 2% gel 3% cc
1st plug sand bottom to 3490' + dump 45x cement
Then squeeze down 8 5/8" surface pipe with
2sx hulls - 2sx gel - 70sx cement - 10 gel - 1 hull -
1 wiper plug - 120sx cement.

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:20 am Day: 28 Month: September Year: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph

Recovered 2406' of 4 1/2" production casing

Maximum pump pressure 875 psi

Shut in pressure 850 psi

Halliburton pumped the cement

Remarks: Mr Paul Luthi received the plugging proposal

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

INVOICED SEP 28 1983

Signed Richard W. Lacey
(TECHNICIAN)

DATE 10-7-83
CONSERVATION DIVISION 9-28-83
Wichita, Kansas

FORM CP-2/3
Rev. 9-82

INV. NO. 5659-W