



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company 9-4-74

Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Cox "A" Well No. 1

Location CNW SW Sec. 9 Twp. 21 Rge. 22 (E) (W)

County Hodgeman Total Depth 4506'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling

Address Box 1082, Great Bend, Kansas License No. 623

Operation Completed: Hour 11:30 AM Day 27 Month 8 Year 1974

The above well was plugged as follows:

8 5/8" to 218' circulated w/ cement. 5 1/2" to 4500' cemented.

Top perforations 4382' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4150' Mud 4150' to 800'

Spotted 70 sacks cement 800' to 350' Mud 350' to 300'

Plug & 70 sacks cement 300' to 0'. Globe Pump Truck.

Pulled 492' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated

DATE 9/4/74

INV. NO. 9822-W

Signed: [Signature]
Well Plugging Supervisor