

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1972

CONSERVATION DIVISION
Wichita, Kansas

10-17-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center, Wichita, Kansas

Lease Name Gus Well No. 1

Location C SE NW Sec. 15 Twp. 21 Rge. 22 (E) (W)

County Hodgeman Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Thomas Drilling

Address Box 400, Duncan, Oklahoma License No.

Operation Completed: Hour 6:45 PM Day 12 Month 10 Year 1972

The above well was plugged as follows:

8 5/8" to 315' circulated w/ cement. Mud 4450' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 300'

Spotted 30 sacks cement 300' to 200' Mud 200' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Halliburton Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edna J. Love
Well Plugging Supervisor

DATE 10/17/72

INV. NO. 6492-U