

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 28 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 083 20 597 (of this well)

Operator's Full Name Ben Hogan  
Complete Address P.O. Box 11276, Ft Worth, Texas  
Lease Name Wieland Well No. 1  
Location 100' E of C. NW SE Sec 22 Twp. 21 Rge. (E) (W) 22  
County Hodgeman Total Depth 4550  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated         
Plugging Contractor Strata Drilling Company  
Address 2421 10th St. P.O. Box 355, Great Bend, Kans. License No.       

Operation Completed: Hour 1:15 AM Day 23 Month Nov Year 1977

The above well was plugged as follows:  
There was 425' of 8 1/2" surface casing.  
1st plug at 900' with 50 lbs of 50-50 pos  
mix. Fill with mud to 400'; 2nd plug  
at 400' with 35 lbs cement 50-50 pos mix.  
Fill with mud to 40'; set bridge with  
Kelly. 3rd plug 40'-0 with 10 lbs 50-50 pos mix  
5 lbs each in rat & mouse hole.  
Accomplished by Halliburton Cementing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Clarence Thomas  
Well Plugging Supervisor

DATE 11-29-77  
INV. NO. 6268-U