

CC: 6-20
M.C.

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-03261-00-00

LEASE NAME NW Beaver Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER T9-W1

330 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR National Cooperative Refinery Assn.

SEC. 5 TWP. 16 RGE. 12 (E) or (W)

ADDRESS Box 6, Great Bend, Ks. 67530

COUNTY Barton

PHONE (316-793-8771) OPERATORS LICENSE NO. 5565

Date Well Completed 9-18-47

Character of Well oil

Plugging Commenced 6-10-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-16-88

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? FOUR (4)

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3287'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	545'	None
				5-1/2"	3287'	1615.97'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 2975' and 5 sacks cement. Shot casing at 2500', 2000', and 1600'. Pulled 50 joints of 5-1/2" casing. Allied squeezed well with 25 sacks ATL cement and 500# hulls, blended in 115 sacks cement. Maximum pressure was 300 psi and shut in 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

8-5-88

(Signature) James W. Rockhold
(Address) Box 698, Great Bend, Ks. 67530

AUG - 5 1988

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1988

STATE NOTARY PUBLIC
IONA M. LEATHERMAN
Barton County, Kansas
My Appl. Exp. 9-26-91

Notary Public
Iona M. Leatherman

COPY

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg, Wichita, Kansas


Company PHIL-H W OIL COMPANY
Farm Staudinger No. 1

SEC. 5 T. 16 R. 12W
SE SW SW

Total Depth. 3296'
Comm. 9-6-47 Comp. 9-18-47
Shot or Treated. Acidized
Contractor.
Issued 4-10-48

County. Barton
KANSAS

K. G. S. LIBRARY



CASING:
8-5/8" 545' Cem. w/275 sx
5-1/2" 3326' Cem.

Elevation. _____

Production. 50 B.O.

Figures indicate Bottom of Formations.

shells, shale & sand	0-325
sand, shale & shells	530
red rock	809
anhydrite	840
shells & shale	1110
salt, shale & shells	1480
lime & shale	1715
lime	2110
shale & lime	2200
lime	2250
lime, shale & shells	2300
lime & shale	2370
shale & shells	2600
lime & shale	2715
lime	2980
lime & shale	3090
lime K.C.	3145
lime	3290
quartzite	3296
Total Depth	

Tops:

Topeka	2690
Heebner	2955
Kansas City	3036
Quartzite	3286

Plug @ 3240
Acid. w/4300 gals.
59 shots 3118-28

RECEIVED
STATE CORPORATION COMMISSION