


15-009-20419-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 5 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE/4 NW/4 NE/4
Lease Owner XXXXXXXXXX BEA DRILLING COMPANY
Lease Name HILGENBERG Well No. A-2
Office Address Box 247 - Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-11 19 69
Application for plugging filed 10-11 19 69
Application for plugging approved 10-11 19 69
Plugging commenced 10-11 19 69
Plugging completed 10-11 19 69
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3310 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud.
Bottom plug set at 540' w/plug & 25 sacks cement thru drill pipe
Come up hole to 40'
Set plug @ 40' with 1/2 sacks hulls & 10 sacks cement
2 sacks cement in rat hole

10-15-69

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas, COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis
Box 823 - Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 14 day of October, 1969

My commission expires April 11, 1970
Blair M. Hague Notary Public.

15-009-20419-00-00

W E L L L O G

DATE COMMENCED:
October 3, 1969

DATE COMPLETED:
October 12, 1969

Bea Drilling Company
HILGENBERG A-2
SE/4 NW/4 NE/4
Section 5-T16s-R12w
Barton County, Kansas

ELEVATION: 1858 K.B.

| | | |
|------|-------|------------------|
| 0 | 55' | Clay & Post Rock |
| 55 | 350' | Clay & Shale |
| 350 | 540' | Sand & Clay |
| 540 | 780' | Red Bed |
| 780 | 807' | Anhydrite |
| 807 | 1330' | Red Bed & Shale |
| 1330 | 1975' | Lime & Shale |
| 1975 | 2460' | Shale |
| 2460 | 2643' | Lime & Shale |
| 2643 | 2926' | Lime |
| 2926 | 2930' | Shale |
| 2930 | 2945' | Lime & Shale |
| 2945 | 2958' | Lime |
| 2958 | 3014' | Shale |
| 3014 | 3024' | Lime & Shale |
| 3024 | 3275' | Lime |
| 3275 | 3286' | Shale |
| 3286 | 3301' | Conglomerate |
| 3301 | 3310' | Sand |
| 3310 | | RTD |

Formation Data

| | |
|----------------|------|
| Anhydrite | 780 |
| Topska | 2643 |
| Heebner | 2926 |
| Toronto | 2945 |
| Douglas | 2958 |
| Brown Lime | 3014 |
| Kansas City | 3024 |
| Base - K.C. | 3275 |
| Conglomerate | 3286 |
| Quartzitic Sd. | 3301 |
| RTD | 3310 |

SURFACE CASING: Set 20#
new 8-5/8" at 577' with
240 sacks cement

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 14th day of October, 1969

My Comm. Expires:
April 11, 1970

Deborah M. Laguer
Notary Public