


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County, Sec. 5 Twp 16S Rge. 12W (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner ISERN-WELLS
Lease Name Staudinger Well No. 1
Office Address Box 486, Ellinwood, Kansas 67526
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 12 19 68
Application for plugging filed November 12 19 68
Application for plugging approved November 12 19 68
Plugging commenced November 12 19 68
Plugging completed November 12 19 68
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3327 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-----|--------|--------|------------|
| Red Bed | | 445 | 783 | 8 5/8" | 490 | NONE |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 350' run 1/4 sack hulls, one plug and 25 sacks cement through drill pipe.
Filled hole with mud to 40' run 1/2 sack hulls, one plug and 10 sacks cement.

Two sacks in Rat Hole.

Job completed 6:00 a.m. 11-12-68

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1968
CONSERVATION DIVISION
Wichita, Kansas

11-13-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ISERN DRILLING COMPANY
Address P. O. Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. F. Banks (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. F. Banks

Box 486, Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 19 68

My commission expires February 10, 1971.

George A. Meyer
Notary Public.

11/18/68 Connected

5-16-12W

9

W E L L L O G

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1968
CONSERVATION DIVISION
Wichita, Kansas

ISERN-WELLS, STAUDINGER #1
SE NW SE, Section 5-16S-~~11W~~ 12W
Barton County, Kansas

ELEVATION: 1860' GL; 1862' DF; 1864' KB.

PIPE RECORD:

8 5/8" set @ 490' with
250 sacks cement.

(DRY & ABANDONED)

ROTARY COMMENCED: 11- 4-68

ROTARY COMPLETED: 11-12-68.

TOPS

Anhydrite 813
Topeka 2656
Heebner 2937
Brown Lime 3026
Lansing 3036

Figures indicate bottom of formation:

0 to 40 clay & rock
205 shale & shells
250 sand
384 shale & shells
411 Dakota Sand
445 shale & shells
783 red bed
1500 shale & shells
1985 lime & shale
2650 shale & shells
2970 lime & shale
3025 shale & lime
3200 lime & shale
3327 lime
3327 Rotary Total Depth


STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.



W. F. Banks

Subscribed and sworn to before me on this 18th day of November, 1968



George A. Meyer, Notary Public



My commission expires: February 10, 1971.