

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,627.00-00

LEASE NAME Hilgenberg "A"

WELL NUMBER 5

SPOT LOCATION SE NE NE

SEC. 5 TWP. 16 RGE. 12 (X) or (W)

COUNTY Barton

Date Well Completed 7-20-84

Plugging Commenced 7-20-84

Plugging Completed 7-20-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR C. F. Krehbiel

ADDRESS P.O. Box 268 Sterling, KS 67579

PHONE # (136 278-2315) OPERATORS LICENSE NO. 5569

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dale Balthazor

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom T.D. 3315

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 780' w/25 sacks cement thru drill pipe

Next Plug: @ 600' w/100 sacks cement thru drill pipe

Top Plug: @ 40' w/1 sack hulls & 10 sacks cement

10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929
Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson

(employee of operator) or

~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

JUL 31 1984
7-31-84
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 27 day of July, 1984

Quincy M. Hague
Notary Public

My Commission expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: July 14, 1984
DATE COMPLETED: July 20, 1984

C. F. Krehbiel
HILGENBERG A-5
SE NE NE
Sec. 5, T16S, R12W
Barton County, Ks.

ELEVATION: 1845 K.B.

0 - 768'	Surface Soil, Post Rock, Shale
768 - 795'	Anhydrite
795 - 2599'	Lime & Shale
2599 - 2622'	Lime
2622 - 2630'	Shale & Sand
2630 - 2916'	Lime
2916 - 2920'	Shale
2920 - 2936'	Lime & Shale
2936 - 2946'	Lime
2946 - 3005'	Shale
3005 - 3017'	Lime & Shale
3017 - 3270'	Lime
3270 - 3315'	Shale, Lime, Chert, Sand
3315'	RTD

FORMATION DATA

Anhydrite	768'
Howard	2599'
Severy	2622'
Topeka	2630'
Heebner	2916'
Toronto	2936'
Douglas	2946'
Br. Lime	3005'
Kansas City	3017'
Base K.C.	3270'
Conglomerate	3277'
RTD	3315'

Surface Pipe: Set used
8-5/8", 28# @582' w/250
sacks 50/50 pozmix, 28 gal.
38 cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 27 day of July, 1984.

My Comm. Expires:
4-29-86

Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1984

CONSERVATION DIVISION
Wichita, Kansas