

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-02101-0000
API NUMBER Nov. 1942 completion

LEASE NAME Stull

WELL NUMBER #1

330 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 5 TWP. 16S RGE. 12 (X) or (W)

COUNTY Barton

Date Well Completed 11-42

Plugging Commenced 10-22-92

Plugging Completed 10-22-92

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757

PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-19-92 (date)

by Dennis Hamel - Hays (KCC District Agent's Name),

Is ACO-1 filed? No If not, Is well log attached? No

Producing Formation L-KC Depth to Top 2882' Bottom 3135' T.D. 3157'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
L-KC	oil, water	0	327	8 5/8"	327	0
		0	3179	5 1/2"	3179	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate 3 holes 800'-B/Anhydrite. Run tubing to 2564'. Pump 75 sx 60/40 - 10% Gel, 200# hulls. Pull tubing to 1562'. Pump 75 sx 60/40 - 10% Gel, 200# hulls. Pull tubing to 824'. Pump 100 sx 60/40 - 10% Gel, 100# hulls. Pull rest of tubing. Pump down casing 50 sx 60/40 - 10% Gel down 8 5/8"-5 1/2" annulus to 400 psi. Plugging complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton

Address Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Sedgwick

Scott W Scheuerman (Employee of Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) P.O. Box 2757, Wichita, KS 67201-2757



SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 92

My Commission Expires: 1-7-95

Notary Public