


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 3 Twp. 21S Rge. (E) 22 (W)
Location as "NE/CNWxSWx" or footage from lines. C/NE SE
Lease Owner California Time Petroleum, Inc. & Strata Drlg., Inc.
Lease Name Moore Well No. 1
Office Address Suite 515 Union Nat. Bank Bldg., 9460 Wilshire Blvd.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Beverly Hills, Calif
Date well completed December 5 19 69
Application for plugging filed December 5 19 69
Application for plugging approved December 5 19 69
Plugging commenced December 5 19 69
Plugging completed December 5 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4349 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0'	288.45'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Plugged at 900' with 80 sacks of cement; plugged at 280' with 30 sacks of cement; plugged at 40' with 15 sacks of cement. Plug down at 5:00 P. M. December 5, 1969.

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1969
CONSERVATION DIVISION
Wichita, Kansas

12-9-69


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas
(Address) 67530

SUBSCRIBED AND SWORN to before me this 8th day of December, 19 69

My commission expires December 8, 1969



Elaine H. Taylor
Elaine H. Taylor Notary Public.

D R I L L E R S L O G

#1 Moore

CASING RECORD: 288.45' of new 8-5/8" surface casing.	COMPANY: California Time Petroleum, Inc. & Strata Drilling, Inc.	DESCRIPTION: C/NE SE Section 3-21S-22W Hodgeman County, Kansas
TOTAL DEPTH: 4349'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2168' KB 2163' GL
	COMMENCED: November 26, 1969	
	COMPLETED: December 5, 1969	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand Post Rock & Shale	0	313	Ran 288.45' of new 8-5/8" surface casing; set and cemented at 288.45' with 190 sacks of regular cement and 2% gel. Plug down at 1:25 A. M. November 27, 1969.
Shale & Shells	313	494	
Sand & Shale	494	1316	
Red Bed	1316	1321	
Anhydrite	1321	1355	
Red Bed, Shale & Shells	1355	1534	
Shale, Shells & Broken Lime	1534	1805	
Shale, Lime & Shells	1805	2196	
Lime & Shale	2196	3887	
Lime	3887	4265	
Lime & Shale	4265	4306	
Lime	4306	4349	
Total Depth 4349'			

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1969
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Ran Electra log.

Plugged hole as follows: Plugged at 900' with 80 sacks of cement; plugged at 280' with 30 sacks of cement; plugged at 40' with 15 sacks of cement. Plug down at 5:00 P. M. December 5, 1969.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 8th day of December, 1969.

My Commission Expires:
December 14, 1969

ELAINE H. TAYLOR
NOTARY PUBLIC
BARTON COUNTY, KANSAS

Elaine H. Taylor
Elaine H. Taylor, Notary Public