

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pawnee County. Sec. 13 Twp 21S Rge. (E) 15 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE SW

Lease Owner Vickers Petroleum Co., Inc.

Lease Name Dupree Well No. 1

Office Address 201 WKH Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 22 19 51

Application for plugging filed August 21 19 51

Application for plugging approved August 21 19 51

Plugging commenced August 22 19 51

Plugging completed August 22 19 51

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 2839 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8 "	900	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug @ 250' dumped 15SX cement filled hole w/ mud to 40'

Set plug @ 40' Dumped 10 SX cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Drilling Co., Inc.

Address 201 WKH Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John M. Little (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *John M. Little*

201 WKH Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27 day of August, 19 51

Allen A. Denton
Notary Public.

My commission expires August 13, 1953



AUG 22 1951
8-28-51

THE VICKERS PETROLEUM CO., INC.

Dupree Well #1
NE NE SW Sec. 13-21S-15W
Pawnee County, Kansas

Casing Record
8 5/8" @ 900' W/425 Sx.

Elevation : 1946 RB
D & A

Commenced: August 9, 1951
Completed: August 22, 1951

LOG

Surface, Soil & Sand	0- 140
Shale & Sand	140- 170
Shale, Shells & Sand	170- 310
Sand	310- 430
Sand, Shale & Red Beds	430- 745
Red Beds	745- 894
Anhydrite	894- 918
Red Beds, Shale & Shells	918-1115
Shale & Shells	1115-1400
Salt, Shale & Lime	1400-1735
Lime & Shale	1735-1960
Broken Lime & Sand	1960-2120
Lime Broken	2120-2160
Shale & Lime	2160-2345
Lime & Shale	2345-2880
Shale & Lime	2880-2939
Lime & Shale	2939-3331
Shale	3331-3400
Lime & Shale	3400-3682
Chert	3682-3737
Shale	3737-3799
Dolomite	3799-3829 TD

Tops:	
Heebner	3296'
Douglas	3331'
Brown Lime	3400'
Lansing	3410'
Viola	3682'
Simpson	3737'
Arbuckle	3799'

RECEIVED
STATE COMMISSION
AUG 28 1951
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this log is true and correct to the best of my knowledge and belief.

The Vickers Petroleum Co., Inc.

By W. P. Simpson

Subscribed and sworn to before me this 27th day of August, 1951.

Allen W. Deaton
Notary Public

My commission expires August 13, 1953.

PLUGGING
 FILE NO. 13-21S-15W
 BOOK PAGE 105-23