

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pawnee County, Sec. 12 Twp. 21 Rge. 15 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Vaughan Drilling, Inc.

Lease Name Barrett "B" Well No. 1

Office Address 1618 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 3/28/68 19

Application for plugging filed 4/2/68 19

Application for plugging approved 3/28/68 19

Plugging commenced 3/28/68 19

Plugging completed 3/28/68 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation ~~clay, sand, & red bed~~ Depth to top ~~xxx~~ Bottom ~~xxx~~ Total Depth of Well 3755 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
sand		0	160			
clay, sand, & red bed			640			
red bed			895			
Anhy.			902	8 5/8"	902'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 300' w/ 1/4 sx hulls & 25 sx cement
Top Plug @ 40' w/ 1/2 sx hulls & 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1968
CONSERVATION DIVISION
Wichita, Kansas

4-3-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Vaughan Drilling, Inc.

Address 1618 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Donald D. Vaughan (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan

1618 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 68

Carolyn Sinning Notary Public.

My commission expires 3/10/71

WELL LOG


COMPANY	Vaughan Drilling, Inc.
CONTRACTOR	Vaughan Drilling, Inc.
FARM	Barrett "B"
LOCATION	NW NE NE Sec. 12-21-15W Pawnee County, Kansas
ELEVATION	1944 KB
SURFACE PIPE	902' 8 5/8" w/400 sx
COMMENCED	3/20/68
COMPLETED	3/28/68

<u>Formation</u>	<u>Depth</u>		<u>TOPS</u>
sand	160'		
clay, sand, & red bed	640	Anhy.	895'
red bed	895	Heeb.	3263
Anhy.	915	Tor.	3276
shale & shells	1830	Doug.	3294
lime & shale	3043	Br.Lm.	3360
lime	3149	Lans.	3372
lime & shale	3230	Vio.	3642
lime	3619	Simp.	3658
lime & chert	3665	Arb.	3702
chert & shale	3680		
lime & chert	3702		
dolomite	3755		


A F F I D A V I T

STATE OF KANSAS
COUNTY OF SEDGWICK

I, Donald D. Vaughan, of the VAUGHAN DRILLING, INC.
being first duly sworn on oath, state that I have knowledge of
the facts, statements and matters herein contained and that the
same are true and correct.


Donald D. Vaughan, President

Subscribed and sworn to before me this 2nd day of April, 1968.


Carolyn Sinning NOTARY

My commission expires: 3/10/71

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1968
CONSERVATION DIVISION
Wichita, Kansas