


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 12 Twp. 21S Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW

Lease Owner Franco Central Oil Company

Lease Name Flick Well No. 1

Office Address Fourth National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 11 19 54

Application for plugging filed June 11 19 54

Application for plugging approved June 11 19 54

Plugging commenced June 11 19 54

Plugging completed June 11 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3786 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LOG ATTACHED						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 270' with heavy mud, set plug and cemented with 20 sacks through drill pipe. Filled hole with mud to 35', set plug and cemented to bottom of cellar with 10 sacks.

6-19-54

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1954
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company

Address 404 KEH Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. E. SMITH (employer or owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. E. Smith

512 Fourth National Bank Building
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 19 54

Rebecca Hill
Notary Public.

My commission expires 10-21-57

PLUGGING
FILED JUN 22 1954
BOOK PAGE 40 LINE 40

THE CARL TODD DRILLING COMPANY
 404 KFH Building
 Wichita, Kansas

FRANCO CENTRAL OIL COMPANY, et al
 #1 Flick
 NE SE NW Sec. 12-21S-15W
 Pawnee County, Kansas

COMMENCED: June 1, 1954
 COMPLETED: June 11, 1954

ELEVATION: 1941 Kelly Bushing

CASING RECORD

0 - 125	Sand and gravel
125 - 335	Shale
335 - 400	Sand
400 - 435	Sand
435 - 535	Shale & shells
535 - 545	Sand
545 - 570	Red Bed, shale & shells
570 - 640	Iron and shale
640 - 704	Red Bed and shells
704 - 905	Red Bed
905 - 925	Anhydrite
925 - 1150	Red Bed and shale
1150 - 1365	Shale and shells
1365 - 1800	Shale and shells
1800 - 1930	Sand, shale and lime
1930 - 2060	Shale and lime
2060 - 2180	Lime and shale
2180 - 2330	Shale and lime
2330 - 2515	Lime and shale
2515 - 2535	Shale and lime
2535 - 2895	Shale and shells
2895 - 3044	Shale and lime
3044 - 3125	Lime and shale
3125 - 3175	Lime and shale
3175 - 3235	Lime
3235 - 3295	Lime
3295 - 3385	Shale and sand
3385 - 3458	Lime
3458 - 3486	Lime
3486 - 3540	Lime
3540 - 3605	Lime
3605 - 3655	Lime
3655 - 3715	Lime and Cong.
3715 - 3761	Lime and shale
3761 - 3786	Lime
3786	Rotary Total Depth

8-5/8" 24# casing set at 704'
 with 350 sacks cement and
 4 sacks CC

TOPS

Topeka	2928
Heabner	3284
Lansing	3399
Conglomerate	3659
Viola	3667
Simpson	3718
Arbuckle	3756

I hereby certify that the above is a true and correct log
 to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By: *Carl Todd*

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 19 1954
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 NE SE NW 12-21S-15W
 404 KFH BLDG
 WICHITA, KANSAS