


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 12 Twp. 81S Rge. 15 (X) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE SE SE
Lease Owner Tatlock
Lease Name Flick Well No. 1
Office Address 111 So. Topeka - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 12 19 51
Application for plugging filed Verbal - 1/9/51 19
Application for plugging approved 19
Plugging commenced 1/12/51 19
Plugging completed 1/12/51 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3772' Bottom 3780' Total Depth of Well 3780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand, Shale & Shells				10-3/4	915'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3780 feet to 250 feet for each plug set.

Plug hole with 20 sacks of cement at 2501' through drill pipe and 10 sacks of cement at 30' to bottom cellar per orders of C. D. Stough to R. W. Rine Drilling Company on 1/9/51.

1-18-51
RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to J. H. Tatlock
Address 111 So. Topeka - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. H. Tatlock (operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Tatlock
111 South Topeka - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of January, 19 51
Madeline Bullinger
Notary Public.

My commission expires February 26, 1951

PLUGGING
FILE SEC 12 T 81 S R 15
BOOK PAGE 54 LINE 35

COPY

U. G. Flick Estate Well No. 1

NE SE SE
Sec. 12-21S-15W
Pawnee County
KansasContractor: The R. W. Rine Drilling Company
Started 12/27/50 Finished 1/10/51LOG

Sand	0 - 160	
Shale & Shells	160 - 530	Syfo @ 500' - O. K.
Red Bed	530 - 860	
Shale & Shells	860 - 905	
Anhydrite	905 - 915	39 Jts. 10-3/4" @ 915' w/750 Sx.
Anhydrite	915 - 935	
Shale & Shells	935 - 1975	Syfo @ 1500' - 1°
Lime	1975 - 2030	Syfo @ 2000' - O.K.
Shale Shells	2030 - 2120	
Shale & Lime	2120 - 2280	
Shale, Lime, Shells	2280 - 2370	
Lime	2370 - 2650	Syfo @ 2500' - 0°
Shale, Lime, Shells	2650 - 2925	
Shale, Lime	2925 - 3000	Syfo @ 3000' - O.K.
Lime	3000 - 3135	
Lime & Shale	3135 - 3198	
Lime	3198 - 3310	
Lime & Shale	3310 - 3400	
Lime	3400 - 3645	Syfo @ 3600' - O.K.
Lime & Shale	3645 - 3755	
Lime, Chert, Shale	3755 - 3780	T.D. D & A

State of Kansas)
County of Sedgwick) ss.

I, E. H. Sloyer, do hereby certify that the above is a true and accurate log of the U. G. Flick Estate Well No. 1, located in NE SE SE, Section 12-21S-15W, Pawnee County, Kansas.

E. H. Sloyer
Secretary**RECEIVED**
STATE CORPORATION COMMISSIONJAN 23 1951
CONSERVATION DIVISION
Wichita, Kansas

Subscribed to and sworn before me this 16th day of January, 1951.

Vira A. McKenzie
Notary Public

My Commission Expires September 18, 1952.

PLUGGING
FILE SEC <u>12-21-15W</u>
BOOK PAGE <u>54</u> LINE <u>35</u>

COPY