


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Paynee County. Sec. 19 Twp. 21 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines. NE/NW/NW
Lease Owner Nadel & Gussman
Lease Name Harrybird Well No. #1
Office Address Box 106, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 2-17 1958
Plugging completed 2-21 1958
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3910' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,304'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3910'.
Plugging started 2-17-58. Finished 2-21-58.
Plugged off bottom with sand to 3650' and dumped 5 sacks cement.
Shot 5 1/2" casing at 3,304'. Pulled pipe out of hole and plugged well as follows: Mudded to 960'. Set rock bridge and dumped 20 sacks cement. Mudded to 300', set rock bridge and dumped 20 sacks cement. Mudded to 40', set rock bridge and mixed 10 sacks for cap on well. Well completed.

MORTGAGE

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas 3-11-58

STATE OF Kansas COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 1958

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGGING
19T. 21 R. 15W
BOOK PAGE 82 LINE 28

WELL LOG

Neibel and Gussman

Harry Bird No. 1

NWc 19-21-15W

Pawnee County, Kansas

Comm: 10-21-52

Comp. 11-5-52

Casing:

8-5/8" 960' w/480 Saz

5-1/2" 3909' w/100 Saz

Formations

Depth

Sand and clay	90
Shale	165
Shale and shells	320
Red bed	386
Sand	495
Red bed	640
Red bed and shale	830
Red bed, shale and sand	945
Red bed and Anhydrite	960
Anhydrite	978
Shale and shells	1000
Lime	1730
Shale and lime	1935
Broken lime	2137
Lime	2200
Lime and shale	2335
Lime	2435
Lime and shale	2795
Shale	2925
Shale and lime	3248
Lime	3389
Shale	3432
Lime	3712
Conglomerate	3764
Shale	3817
Lime	3910

Geological Time

Anhydrite	945
Hoerner Shale	1351
Brown Lime	3432
Lansing-K.G.	3557
Conglomerate	3713
Viola	3717
Simpson Shale	3762
Aruckie	3809
E.O.	3910

19 21 15W

82 28

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss:

L. C. Hay, of lawful age, deposes and states that the above forma-
tions and depths are correct as shown by the daily drilling log
of the Harry Bird No. 1 in the NWc of 19-21S-15W, Pawnee County,
Kansas.

L. C. Hay

XX

Subscribed and sworn to before me this 10th day of November, 1952.

Paula Dady

Notary Public

My commission expires Nov. 3, 1956.