


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Pawnee County, Sec. 21 Twp. 21 Rge. 15 (E) (W)
Location as "NE/CNWKSWK" or footage from lines C/SF-SF 660' from S. 660' from E
Lease Owner L. D. Davis/ L. D. Drilling, Inc.
Lease Name Kasselman Well No. 1
Office Address Route 1, Box 183-B, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 07/19 1983
Application for plugging filed 09/26 1983
Application for plugging approved 09/26 1983
Plugging commenced 09/26 1983
Plugging completed 09/28 1983
Reason for abandonment of well or producing formation not commercial

If a producing well is abandoned, date of last production 08/15 1983
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey
Producing formation Conglomerate sand Depth to top 3545 Bottom 3546 Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8 5/8"	Surface	918			0
	4 1/2"	Surface	3899			2406'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 3570'. Perforations at 3545' to 3546'. Sanded pipe to 3460'.
Dumped 4 sacks cement with dump bailer on top of sand. Wellex cut pipe at 2406'. Pulled pipe. 09/28/83 Halliburton pumped 2 sacks of hulls, 10 sacks gel, 70 sacks cement, 10 sacks of gel, 1 sack of hulls, put it 8 5/8" plug, pumped 120 sacks cement 60-40 poz, 2% gel 3% CC.
Plug down time 10:20 am
Pump pressure 500-900 pounds
Shut in pressure 850 pounds

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1983

CONSERVATION DIVISION
Wichita, Kansas

10-5-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D. S. & W Well Servicing, Inc. Lic. no. 6901, Unit 1004
Address P. O. Box 231, Claflin, Kansas 67525

STATE OF Kansas, COUNTY OF Barton, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J. Strick

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 1983

Harlyn Beck
(Address)

My commission expires 9-21-86

Notary Public.

