

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Beck

~~J. P. Roberts~~
~~Assistant Director-Administrator~~
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Co., Inc.
Complete Address: Box 349 Russell, Kansas 67665
Lease Name Prosser "B" Well No. 3
Location SE SW SW Sec. 36 Twp. 21 Rge. (E) (W) 16
County Pawnee Total Depth 4159'
Abandoned Oil Well Gas Well Input Well SWD Well ~~SWD~~ D & A _____
Other well as hereafter indicated: _____
Plugging Contractor: Forbes Casing Pulling Co.
Address: Box 221 Great Bend, Kansas License No. 637
Operation Completed: Hour 12 N Day 15 Month 2 Year 1971

The Above well was plugged as follows:

Total Depth 4159' 8 5/8 csg set at 959' cwc 450 sk.

5 1/2 csg set at 4038' cw 125 sk cmt.

5 1/2 csg PBTB 4014' with perf. (3863-3872)

Sand pump lost in hole - top of fish 2700'

Pushed 5 1/2 plug to 2700' poured sd (20 gal) Dumped 5 sk cmt W/dump bailer. (2627=2700)

Recovered 2600' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/2 sk hulls, release plug and
pumped 100 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/18/71

INV. NO. 3359-W

Signed: Leo Massey
Well Plugging Supervisor