

15.145.20238-0001

~~KANSAS~~

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 24 1975  
2-24-75  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Barnett Oil, Inc.

Complete Address 411 First Natl. Bank Bldg., Wichita, Kansas 67202

Lease Name Prosser (OWWO) Well No. 1

Location NE SW SE Sec. 36 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3912'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Pipe Pullers, Inc.

Address Nox 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 4 P Day 21 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3912' 8 5/8 csg set at 945' cwc 500 sk.

4 1/2 csg set at 3912' cw 125 sk cmt.

4 1/2 csg PBTB 3890' with top perf. (3869')

Filled 4 1/2 csg with sand (3890-3800) Set 4 1/2 wood plug at 2940' -dumped 4 sk cem.

Cutoff & recovered 2891' of 4 1/2 csg.

Filled 8 5/8 csg with mud to 325' -set rock & sand bridge (325-300)

Filled with RM cement from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 2/27/75

INV. NO. 882-W