

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
FEB 18 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mill Drilling Co., Inc.

Complete Address Box 349 Russell, Kansas 67665

Lease Name Prosser Well No. B -1

Location SW SW SW Sec. 36 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3917

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 11 A Day 15 Month 2 Year 1971

The above well was plugged as follows:

Total Depth 3917' 8 5/8 csg set at 672' cwc 350 sk.

5 1/2 csg set at 3909' cw 100 sk cmt.

5 1/2 csg PBTD 3911' with perf. (3844)

Filled 5 1/2 csg W/sd (3800-3911) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Cutoff and recovered 3100' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/2 sk hulls, release plug and
pumped 100 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben J. Messing
Well Plugging Supervisor

INVOICED

DATE 2/18/71INV. NO. 3358-W