

15.145-00538-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Warren Hill

Complete Address Box 984 Great Bend, Kansas 67530

Lease Name Harms Well No. 1

Location NE NE NW Sec. 36 Twp. 21 Rge. (E) (W) 166

County Pawnee Total Depth 3940'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3:30 P Day 4 Month 6 Year 1973

The above well was plugged as follows:

Total Depth 3940' 8 5/8 csg set at 967' cwo 500 sk.

4 1/2 csg set at 3843' cw 200 sk cmt.

4 1/2 csg PBTD 3809 Perf. unknown.

Filled 4 1/2 csg W/sd (3750-3809) dumped 4 sk cmt W/dump bailer. (3715-3750)

Cutoff and recovered 2639' of 4 1/2 csg.

Mud to 375' -rock & sand bridge (350-375)

Dumped 5 yds readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/7/73
INV. NO. 9464-U

Signed: Ben F. Messing
Well Plugging Supervisor