

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Co., Inc.

Complete Address 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name Hewson Well No. 1

Location S/2 SE NW Sec. 28 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3860'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Glebb & Smith Pipe Pulling

Address Box 156 Ellinwood, Kansas 67526 License No. 396

Operation Completed: Hour 11:30 A Day 26 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 3860' 8 5/8 csg set at 1030' cwc 400 sk.

5 1/2 csg set at 3853' cw 100 sk cmt.

Pumped down 5 1/2 csg with 100 lbs hulls and 25 sk cmt -top of cmt 3180' - 2000 lbs. Pres.

Cutoff and recovered 3161' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs hulls, released 8 5/8 plug

& pumped 120 sk 50-50 poz cmt. 300 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: R. J. [Signature]  
Well Plugging Supervisor

INVOICED

DATE 12/27/72

INV. NO. 6981-10