



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 134-2

LOCATION C NE NE SW

SEC. 28 TWP. 21 RGE. 16W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Cora Brown

Operator Sunray Oil Corp. Address Box 195  
Great Bend, Kansas

Field Wildcat County Pawnee

Total Depth 3875 1/2' Feet.

(Describe briefly the manner in which the well was plugged)

From 3800' to 3853' filled with rocks. From 3853' to  
 3824', 4 sacks cement. Mud from 3824' to 2816'. Bridge  
 set at 2816' to 2798' with rocks and 2 sacks cement. Mud  
 in hole from top bridge to 265'. Rock bridge from 265' to 250'.  
 20 sacks cement from 250' to 190'. Mud to 50', rock bridge  
 to 35' sand 10 sacks cement to bottom of cellar. Cellar filled  
 in with dirt.

**PLUGGING**  
 FILE SEC 28 T 21 R 16W  
 BOOK PAGE 134 LINE 8

E. D. Stealy - N  
 District Conservation Agent  
 Date 8-1-50 Conservation Div.

AUG 8 - 1950 8-8-50  
 STATE CORPORATION  
 COMMISSION