

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 5

LOCATION ~~#27~~ SWSE

SEC. ~~7~~ TWP. 16 RGE. 12

*Bad Hole Cabel Tool*

Dry Hole            Abandoned Oil Well — Abandoned Gas Well —

I have today completed supervision of plugging of:

Well No. 1 Lease Mand.

Operator M B Armor Address Wichita Kan

Field — County W Barton

Total Depth 1935 Feet.

(Describe briefly the manner in which the well was plugged)

*This hole went bad & was abandoned at 1935 ft  
Filled with heavy mud 1935 to 800 ft bridge  
cemented with 17 sack cement 300 ft to 270 ft  
heavy mud 270 to 15 ft cement into collar base  
with 25 sack cement.*

*H. W. Kerr* 4-18-45  
District Conservation Agent

Date Apr 12-45

PLUGGING  
FILE SEC. ~~7~~ 16 R 12 W  
BOOK PAGE 10 LINE 21

M. B. ARMER  
 508 Bitting Building  
 Wichita 2, Kansas.

Co.-Black-Marshall Oil Company  
 County: Barton  
 State: Kansas.  
 Location: CWL SW $\frac{1}{4}$  SE $\frac{1}{4}$  Sec. 9-16S-12W.  
 Farm: J. P. Mans # 1  
 Commenced: 12/20/44  
 Completed: 1/18/45 abandoned. 3/2/45. (Dry)  
 Elevation: 1895 ft.

Casing Record  
 12 $\frac{1}{2}$ " 400  
 10 " 820

Cellar	8	Shale Blue	1135
Post Rock	11	Shale Gray	1145
Shale	90	Shale Blue	1160
Shale	180	Shale & Shells	1225
Shale	245	Shale	1235
Shale	310	Lime	1245
Shale	350	Salt	1265
Blue Shale	360	Salt	1425
Sandy "	370	Salt	1440
" " 2 BW 360-370	400	Shale Blue	1450
run 12 $\frac{1}{2}$ "		Salt	1465
Shale	445	Salt	1500
Shale Sandy	490	Lime	1505
Shale	515	Lime	1510
Shale	542	Shale & Shells	1545
Iron	548	Lime	1555
Shale	550	Shale & Shells	1670
Shale Red Blue	565	Lime	1595
Shale Red	580	Shale Light	1600
Red Shale Red	615	Lime	1650
" " "	645	Shale & Shells	1675
Red Rock	685	Lime	1690
Shale Red	710	Lime (filling up hole	1740
Red Shale	740	drilling out)	1775
Red Shale	760	Shale Broken	1800
Shale Red	770	Lime	1810
Blue Shale	780	Shale Shells	1865
Red Shale	795	Lime ( R.S.S.) 1 BW 1865	1865 T.D.
Shale Red	805	Lime ( filling hole up to	
Lime ( T. Anhydrite 805'	810	1825- drilling out	
Lime run 10"	820	same )	
Lime	835	Lime ( bottom w/bailer 1872 )	1885
Shale Red	875	Lime	1895
Red Shale	920	Lime Sandy	1900
Red Shale	990	Shale Blue	1905
Red Shale	1000	Lime (Straightening up hole)	1910
Red Shale	1030		1920
Blue Shale	1080		1932 T.D.
Red Rock R.S.S.	1100		
Shale Red	1115		

Fishing for Tools and trying to  
 Straighten Hole.  
 Well Abandoned and Plugged.

**PLUGGING**  
 FILE SEC 9-T-16-12W  
 BOOK PAGE 10 LINE 21