

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 69-22
 LOCATION 8W-8W-11W
 SEC. 9 TWP. 16 RGE. 12

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Surgeon "A"
 Operator St. Bend Pipe & Supply Co. Address Box 414 St. Bend Kans.
 Field _____ County Barton
 Total Depth 3326 Feet.
 Plugging Contractor West Supply Co, Inc.
 Plugging Contractor's License No. 14
 Address Chase Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 800' no Cem. 5 1/2" set 3321'
 w/75 sq Cem. Sanded hole to 3315' dumped 5 sq
 Cem. Shot off and pulled 5 1/2" casing. Shot
 off and started 10 3/4". Pumped in 15 sq fresh
 fell mud. spotted 65 sq Cem at 250' thru
 10" pulled pipe mudded hole to 25' set bridge
 and cemented to surface w/15 sq Cem.
 Pumping by Globe Cem. Co.

Warren H. Warner
 District Conservation Agent

Field 10-22-54

Date OCT 20, 1954

PLUGGING
 FILE SEC 9-T-16-R-12W
 BOOK PAGE 69 LINE 22