

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Oil Co., Inc.

Complete Address Suite 550 200 W. Douglas Wichita, Kansas 67202

Lease Name Turgeon Well No. 11

Location CSL SW Sec. 9 Twp. 16 Rge. (E) (W) 12

County Barton Total Depth 3349'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend Kansas 67530 License No. 399

Operation Completed: Hour 12:30 P Day 16 Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3349' 15 1/2 csg set at 480'

6 5/8 csg set at 3303' W/5" liner (3241-3341)

Set plug at 2800' ^{sd--} poured 340' Dumped 5 sk cmt W/dump bailer. ((2755-2800))

Cutoff and recovered 2030' of 6 5/8 csg.

Pulled csg to 460' pumped 15 sk gel & water W/100 lbs hulls--pulled csg to 305'--

displaced 75 sk cmt--pulled csg to 210'--pumped 10 sk gel & water --displaced

50 sk cmt.--pulled remaining csg--set rock & sand bridge (25'-40') filled from

25' to base of cellar with 25 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 7/18/73
INV. NO. 7650-W