

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 90-10  
LOCATION Cw/2-W/2-SW  
SEC. 9 TWP. 16 RGE. 12W

Dry Hole \_\_\_\_\_ Abandoned Oil Well ✓ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 5 Lease Surgeon

Operator Sunray Oil Corporation Address Box 195, Great Bend Ks.

Field \_\_\_\_\_ County Barton

Total Depth 3225 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 1/2" @ 812' C.W.C. 5 1/2" set 3224' w/ 150# Cem.  
P.B. to 3215' top Ref. 2953' Sand to 2940' dump 5  
st Cem. shot off and pulled 5 1/2" casing. Filled  
hole with heavy mud to 260' set rock bridge  
and run 20 st Cem. mud to 35' rock bridge  
and 10 st Cem. to base of cellar

Warren H. Horner  
District Conservation Agent

Date Comp Jan 22, 1955

**PLUGGING**  
FILE SEC 9 T 16 R 12W  
BOOK PAGE 90 LINE 10

1-25-55