


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SE-SE

SEC. 9 TWP. 16 RGE. 12W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Maus

Operator A. P. Touch Oil Co. Inc. Address 7301 S. Broadway - Wichita - Kans.

Field _____ County Barton

Total Depth 2374 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 228 ft. Circulated with cement.
5 1/2 casing at 3373 ft - Lane Wells Plug at 3229 ft
2 sacks of cement on top of Plug - Filled with sand
& chert from 3229 ft to 3075 ft. Mixed 5 sacks of
cement at 3075 ft - Shot off & Pelled the 5 1/2 casing -
Filled with sand to 288 ft. Rock Bridge &
20 sacks of cement at 288 ft. Mixed to 39 ft
Bridge & 10 sacks of cement at the surface

4-21-50

C. M. Stough

District Conservation Agent
Date 4-19-50

PLUGGING
FILE SEC 9-T-16012W
BOOK PAGE 1 LINE 41

X