

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-009-22,383.0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Valley Oil, Inc.

Complete Address 1017 Harrison, Great Bend, Kansas 67530

Lease Name Luerman Well No. 1

Location S2 N/2 NE SW ANOVA Sec. 8 Twp. 16 Rge. 12 ~~XXXX~~ (East) (West)

County Barton Total Depth 3369'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Emphasis Oil Operations and Allied Cementing Co., Inc.

Address Box 506, Russell, Kansas License No. _____

Operation Completed: Hour: Noon Day: 2 Month: June Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-296'-175 sacks

Hole circulated and filled with mud. 50 sacks cement pumped through

drill pipe at 540'. 30 sacks cement pumped through drill pipe at 300'.

Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and

hole cemented to base of cellar with 10 sacks cement. Rathole cemented

with 10 sacks cement. Cement used: 50-50 Pozmix w/4% gel and 3% CC.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 4 1981

06-04-81

I hereby certify that the above well was plugged as herein stated CONSERVATION DIVISION

INVOICED

Signed: [Signature]
Wichita, Kansas
Conservation Division Agent

DATE 7-27-81

INV. NO. 6022-W