

KANSAS

Form CP-3  
Rev. 6-9-67

*4*  
STATE CORPORATION COMMISSION

15-009-15707-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Keener Oil Company or David A. Bartlett  
 Complete Address 406 National Bk. of Tulsa Bldg.,  
Tulsa, Oklahoma, 74103

Lease Name Luerman Well No. # 2

Location C E/2 NE SW Sec. 8 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3312

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Forbes Casing Pulling, Inc.

Address Rox 221, Great Bend, Kansas 67530 License No. # 49

Operation Completed: Hour 1:30 PM Day 8 Month 2 Year 1968

The above well was plugged as follows:

No surface pipe.  
 Sanded hole back to 3300' & dumped 5 sax cement with dump boiler. Circulated hole  
 with mud @ 600'. Pulled pipe to 500' & displaced 50 sax cement. Pulled pipe to  
 250' & displaced 30 sax cement. Pulled remaining pipe & displaced 40 sax cement  
 with Sun Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Luerman  
Well Plugging Supervisor

DATE 2/13/68  
INV. NO. 7262-W