

DISTRICT CONSERVATION AGENT'S REPORT

15-009-15697-0000

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 135-44

LOCATION SEC-SE-21E

SEC. 8 TWP. 16 RGE. 12-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Bushnell "A"

Operator Northern Ordnance, Inc. Address Box #317 - G. Beach, Kans.

Field _____ County Barton

Total Depth 3344 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 800ft. not cemented
8 5/8 - 2505ft not cemented - 5 1/2 casing set at 3339ft -
cemented with 60 sacks of cement. Lane Wells Plug at 3080ft
Filled with sand to 3050ft - dumped 5 sacks of cement
at 3050ft. Filled hole with heavy mud - (Shot of & Pulled
the 5 1/2 casing - Shot of & hulled 1525ft of 8 5/8 casing -
Shot of & hulled 275ft. of 10 3/4 casing - Set rock bridge
& 135 sacks of cement at 275ft. mud to 30ft. bridge &
15 sacks of cement at the surface
Northern Ordnance, Inc. Plugging Contractors

RECEIVED C. H. Stouck -
District Conservation Agent

Date 1-27-52

FILED
FILE NO. 8716 R1W
BOX FILE 135-14044

01-30-52